

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970, LIBER 1

PAGE 384
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T-7-S R-4-E	G-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

7 DEC 1999 1:05:39 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher set 1/4 Sec. post W. Ash 12 S 27 E 16 Beech 6 S 39 W 17
1886 James Blair dug a large hole but didn't find anything. He set a cedar post, ashes, 3 bricks & stone 50 links west from a hole where a fence post formerly stood. Franklin Wright & Patrick Lennon being sworn said that they saw the distance measured from said fence post and knew it to be 50 links.
1964 I dug through the pavement and found pieces of brick and crockery and set a 1/2" X 4' iron pipe
1973 I found the iron pipe and recorded it in Liber 2, Page 541
April 1998 Found 1/2" X 3' iron pipe and bricks and witnessed prior to road re-construction. Replaced pipe with 5/8" X 3' re-rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 9, 1999 Found 5/8" X 3' re-rod under new asphalt pavement as per witnesses taken in 1998. Set Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful re-establishment and perpetuation of the position of the original corner.

dbl. hd. nail and disc in E.P. S 40° E 41.49
dbl. hd. nail and disc in E.P. S 50° W 47.46
dbl. hd. nail and disc in E.P. N 10° W 149.05
S.W. corner of concrete slab over well N 65° E 85.19



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040