

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 39

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - 7 - 5 R - 4 - E	K - 4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
DEC 05 1994 2:01 P.M.
LENAWEE COUNTY
JEANETTE D. P'NOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on November 14 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set 1/4 sec. post Ironwood 5 N 78 W 19, Ironwood 6 N 2 E 17
 March 1884, James Blair Found Iron and stone 49 1/2 lks South of S. rail of RR.
 September 1966, I found 1/2" X 2" strap iron 32.7 South of S. rail and raised to the surface with iron pipe.
 April 1973, K.L. Suydam found iron pipe and recorded it in L. 2, P. 393.
 March 1978, I found and used the iron pipe and recorded it in L. 4, P. 80.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 14, 1994, found iron pipe under 3" of asphalt.
 November 28, 1994, Replaced iron pipe with 3/4" X 3' iron pipe in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 SE. Corner of house foundation N 30° W 123.42
 Fd. dbl. hd. nail & disc in North face Elec. pole S 65° E 110.82
 Fd. dbl. hd. nail & disc in East face Elec. pole S 30° W 50.25
 Cut "X" on East end 12" C.M.P. N 45° E 31.48
 Corner is 22 feet North of the center line of Deerfield Road.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 14, 1994
 Signed by Glenn E. Richard Date Nov. 29, 1994
 Glenn E. Richard
 Surveyor's Michigan License No. 13040