

MAY 16 1997

Filed under Remonumentation Act 345 of 1990 LIBER 1 PAGE 143
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

3 DEC 96 3:20 P.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Lenawee Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T - 7-S R - 4-E _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 12 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, June 1819, Joseph Fletcher set post cor. Sec. 1 & 12, Elm 40 N 33 E 14, W. Ash 10 S 59 W 21
 Couldn't find any record of James Blair ever finding this corner.
 April 26, 1955, W.E. Sommer & I measured East to the occupied line at the North 1/4 corner of Section 7, T7S-R5E and West to a found iron called for in J.L. Richard's records. Using a combination of the GLO Plat and J.L. Richard's records. We re-established the corner but the notes don't describe the type of monumentation.
 1978, I found an iron pipe and witnessed it prior to the road commission paving over it.
 1989, K.L. Suydam found the iron pipe and used it on a survey west of the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 12, 1996, I found the iron pipe under new asphalt pavement. Replaced it with a 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box after digging deeper but did not find anything else.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Iron pipe capped #17636 West 32.97
 Fd. dbl. hd. nail & disc in Elec. pole N 85° W 76.41
 "X" cut on North end C.M.P. S 50° W 17.01
 "X" cut on South end C.M.P. S 15° W 50.55
 Iron pipe at A-3, T7S-R5E, North 66.00 (not corrected to Town line)



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 8, 1996

Signed by Glenn E. Richard Date 11-25-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040