

**SURVEY &
REMONUMENTATION**

APR 28 1995

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **40**

or corners in
Lenawee Located In: Corner Code #

(County)

Public Land Survey T-7-S R-4-E M-4
 T R
 T R
 T R

Property Controlling S T R
 in Section S T R
 Miscellaneous S T R
 Property in Sec. S T R

FILED
 DEC 05 1994 2:01 P.M.
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Glenn E. Richard, in a field survey on November 14 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set 1/4 sec. post Poplar 10 N 74 E 15, Beech 20 S 18 E 18
 March 1884, James Blair "Found Iron" and again in August of 1890 when he described the corner as stake with stones and 3 iron bars around.
 November 1924, Walter Frazier, R.L.S. 2268, found irons 48.5 South of S. rail.
 June 1968, I found wood stake over iron rod 18" deep and raised with iron pipe.
 May 1973, K.L. Suydam P.S. 17636 found iron pipe and recorded it in L.2, P. 359.
 October 1981, G.E. Richard P.S. 13040 found iron pipe and recorded it in L. 5, P. 20.
 November 1981, I raised to surface with 60d spike over iron pipe.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 14, 1994, found 60d spike.
 November 28, 1994, found 60d spike over iron pipe. Replaced iron pipe with 3/4" X 3' iron pipe in monument box.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 NE. Corner of porch S 55° W 111.60
 NE. Corner of porch S 65° W 95.25
 SW. Corner of house foundation S 35° E 121.92
 Fd. P.K. nail in NE. face of Elec. pole S 60° W 30.45
 W. 1/4 corner Sec. 7, T7S-R5E North 39.63
 Corner is 1.8 North of centerline of Deerfield Road.



Witnessed by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 17, 1994
 Witnessed by Glenn E. Richard Date Nov. 29, 1994
 Surveyor's Michigan License No. 13040