

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 **LIBER 1 PAGE 205**

SECTION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7 - S</u> R <u>4 - E</u>	<u>M - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

17 OCT 97 3:53 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 04, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher set post cor. Sec. 12 & 13 Lynn 12 N 21 W 19 Sugar 12 S 31 E 23
 1890 James Blair found the old stake
 Early 1900's J.L. Richard records "Iron & stones" and same witnesses as Blairs
 19 J.L. Richard Found drag tooth placed tile over same
 1968 I dug and found a tile and rust spot in the sub soil where the iron had been and set iron pipe
 1973 K.L. Suydam found iron pipe and recorded it in L 2 P 391
 1981 I found the iron pipe which checked the one 1968 witness and recorded it in L 5, P20.
 Blairs record distance between M-4 & 5 is 2650.56 Measured 2651.18.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1997 I found the iron pipe and replaced it with a 3/4" X 3' iron pipe capped G.E.R. 13040
 Sept. 5, 1997 Set monument box after Len. Co. Rd. Comm. layed new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. in monument box and is accepted as the best available evidence of the position of the original corner.

- Found dbl hd nail & disc in 40" Ash N 30° W 58.33
- Found dbl hd nail & disc in 26" Maple (stump) N 80° E 24.88
- Found dbl hd nail & disc in 30" Maple S 25° W 111.23
- Found dbl hd nail & disc in 30" Maple West 24.32
- 3/4" iron pipe in monument box @ A-5 T7S R5E North 3.96



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 30, 1997

Signed by Glenn E. Richard Date Oct. 7, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040