

SURVEY & REMONUMENTATION

JAN 15 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 206
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T - 7 - S R - 4 - E	M - 6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

17 OCT 97 3:53 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 04, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1819 Joseph Fletcher set 1/4 Sec. post Beech 12 N 58 W 18 Beech 12 S 55 E 19
- 1882 James Blair "Found Stake and bricks"
- 1889 James Blair Found Stake and "Set new stake and bricks"
- 1935 Walter Frazier "Found old stake & bricks. Drove I.P."
- 1973 Assoc. Eng. & Surveyors dug large hole (iron was gone) Found bricks & dark spot and rust from iron.
- Set 1" X 4' iron pipe capped 12030
- 1984 Werner Sommer "Found iron pipe" and recorded it in L 5, P 136.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Sept. 4, 1997 I found a 3/4" X 40" iron pipe which checked the recorded witnesses and replaced it with a 3/4" X 3' iron pipe capped G.E.R. 13040. Saw traces of the brick when I removed the found iron pipe.
- Sept. 6, 1997 Set monument box after Len. Co. Rd. Comm. layed new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Found dbl hd nail & disc in H-frame pole S 85° W 34.66
- Found dbl hd nail & disc in H-frame pole S 60° W 39.70
- Found dbl hd nail & disc in H-frame pole S 25° W 83.02
- Found dbl hd nail & disc in R. R. tie post N 65° E 27.63
- 3/4" iron pipe in monument box at A-6 T7S R5E North 12.55



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 30, 1997

Signed by Glenn E. Richard Date Oct. 7, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040