

SURVEY & REMONUMENTATION

JAN 15 1998

LIBER 1 PAGE 208

Filed under Remonumentation Act 345 of 1990

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 OCT 97 3:54 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

For corners in

Lenawee
(County)

Located In:

Corner Code #

1. Public Land Survey		T - 7 - S	R - 4 - E	M - 8
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec	S	T	R	
	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 04, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher set 1/4 Sec. post Sugar 12 N 30 E 15 Sugar 10 N 70 W 25
Did not find any information on this corner in either J. Blair or J.L. Richard's records
1967 I dug but didn't find anything. I re-established the corner (iron pipe) in line with remains of old end post west and by proportioning distances between fence posts on occupied lines N. & S. going west along the occupied 1/4 line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1997 I found the 1/2" X 20" iron pipe 2' +/- East of pavement centerline and is 10.5 East of line between M-7 & M-9 and replaced it with a 3/4" X 3' iron pipe capped G.E.R. 13040
Sept. 6, 1997 Found traces of tile when digging hole for monument box after Len. Co. Rd. Comm. layed new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

12" boat spike in drive 3' west of pave West 15.73
Telephone pedestal N 15° W 105.5
"X" cut on face of 3 1/2" steel post N 30° E 36.28
Survey mark spike & re-mon tag in 40" oak S 10° E 195.87

3/4" iron pipe in monument box @ A-8 T7S R5E North 33'



Ratified by Peer Group in accordance with P.A. 345 Co. Rep Glenn E. Richard Date September 30, 1997

Signed by Glenn E. Richard Date Oct. 7, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040