

**SURVEY &  
REMONUMENTATION**

**JAN 15 1998**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 1 PAGE 209**

**SECTION**

STATE OF MICHIGAN  
LENAAEE COUNTY  
FILED

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 4 - E	M - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

17 OCT 97 3:54 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on September 04, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. 1819 Joseph Fletcher Elm 12 stands for cor. Sec 24 & 25  
Early 1900's J.L. Richard record "Stake in tile 2 rods W. from fence"  
1967 I dug and found stake and tile and added an iron pipe  
1978 I found the iron pipe under the pavement, raised with 60d spike and recorded it in L 4, P 49  
"X" on CMP S 15 E 66.28 "X" on CMP S 20 W 61.54

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Sept. 4, 1997 Found 60d spike over 1/2" X 25" iron pipe. Replaced it with 3/4" X 3' iron pipe capped  
G.E.R. 13040  
Sept. 8, 1997 Found top of tile (on end) when digging hole for monument box after Len. Co. Rd. Comm.  
laid new asphalt pavement. The top of the tile is 0.05 above the inside bottom of the box

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Fd "X" cut on CMP S 20° E 66.28  
Fd "X" cut on CMP S 15° W 61.57  
Fd dbl hd nail & disc in 24" Mulberry N 45° W 20.52  
Cut "X" on N. end C.M.P. N 10° W 127.72  
Survey mark spike & re-mon tag in E.P. N 10° E 164.56  
3/4" iron pipe in monument box at A-9 7-5 North 41.33'



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 30, 1997

Signed by Glenn E. Richard Date Oct. 7, 1997  
Glenn E. Richard

Surveyor's Michigan License No. 13040