

REMONUMENTATION
 MAY 16 1997
 COMMISSION

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7-S R 5-E A-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

3 DEC 96 3:19 P.M.

JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 13 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not established on the original government surveys.
 1907 J.L. Richard survey notes "Corner lost". Set new corner from remains of old sluice said to be over old corner 13 1/4 links S. of s. rail & 60 1/2 links N. of M-4, T7S-R4E (iron rod, tile & bricks)
 April 1955, W.E. Sommer & I dug and found iron rod and tile, raised to surface with hex iron.
 October 1981, I found the hex iron and recorded it in L. 5, P. 19
 Nov. 1985, The road commission had removed the tracks and the hex iron. I set a RR. spike from the previously recorded witnesses and recorded it in L. 5, P. 152.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 13, 1996, I found the RR. spike under 3" of asphalt 0.45 East of the Town line. Also found bricks 18" deep. I set 3/4" X 3' gas pipe capped G.E.R. 13040 in a monument box on the Town line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the corner.
 NW. corner of brick fireplace Hse. #9105 S 50° E 147.70
 NE. corner of conc. block found. Hse. #8997 S 35° W 142.77
 NE corner of conc. block porch found. Hse. #8997 S 40° W 120.52
 SE. corner of conc block porch found. Hse. #8540 N 40° E 109.45
 M-5, T7S-R4E (recorded in Re-mon L. 1, P. 40) South 39.63



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 8, 1996
 Signed by Glenn E. Richard Date 11-25-96
 Glenn E. Richard
 Surveyor's Michigan License No. 13040