

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 210

SECTION

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

17 OCT 97 3:55 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located in:	Corner Code #
Lenawee (County)		
1. Public Land Survey	T - 7 - S R - 5 - E	A - 5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on Oct. 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher Intersect W. Bdg. 6 lks S. of post. Set post at intersection cor. sec. 7 & 18 Poplar 9 S 59 W 22 W. Oak 20 S 10 W 24.
 NOTE THE CONFLICT WITH GLO JOG as to direction of falling
 The record in J.L. Richard's book prior to his 1907 survey call for "iron 6 lk N. of Palmyra cor.
 1907 J.L. Richard "Found iron 6 lks N. of Palmyra corner
 1968 I dug and found the Palmyra Twp. corner M-5 T7S, R4E by using a survey done by James Blair in 1890
 1989 I set a 3/4" re-rod 6 lks (3.96') north of M-5 T7S, R4E and recorded it in L 5 P 201. The occupation agreed with the 6 lks north.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1997 Found 3/4" re-rod in the pavement
 Oct. 8, 1997 Dug through new asphalt pavement & found 3/4" re-rod. Replaced the re-rod with 3/4" X 3' iron pipe capped G.E.R. and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. in monument box and is accepted as a careful & faithful re-establishment of the position of the original corner.

- Found dbl. hd. nail & disc in 40" Ash N 20° W 54.66
- Found dbl. hd. nail & disc in 26" Maple stump East 24.65
- Found dbl. hd. nail & disc in 30" Maple S 10° W 115.11
- Found dbl. hd. nail & disc in 30" Maple S 80° W 24.66

3/4" iron pipe in monument box @ M-5 T7S R4E South 3.96



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 30, 1997

Signed by Glenn E. Richard Date Oct. 9, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040