

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

LIBER 1 PAGE 211

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T -7- S R -5- E	A - 6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 OCT 97 3:55 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 06, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set on the G.L.O. survey
1882 James Blair "Found stake north and 1 1/2 lks west of Palmyra corner"
1935 Walter Frazier "Found old stake hole 19 lks (12.54') N. of Palmyra corner & 1 1/8 lks W. Drove I.P."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1997 I found a iron pipe in the pavement 12.55 N. of the corner M-6 T7S, R4E on the township line.
Sept. 6, 1997 Replaced the found iron pipe with a 3/4" X 3' iron pipe capped G.E.R. 13040 and monument box after Len. Co. Rd. Comm. layed new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E. R. 13040 in monument box and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- Found dbl hd nail & disc in H-frame pole S 20° W 94.57
- Found dbl hd nail & disc in H-frame pole S 45° W 47.07
- Found dbl hd nail & disc in H-frame pole S 70° W 37.85
- Found dbl hd nail & disc in RR tie post East 25.05

3/4" iron pipe in monument box at M-6, T7S, R4E, South 12.55



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 30, 1997

Signed by Glenn E. Richard Date Oct 7, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040