

SURVEY & REMONUMENTATION

JAN 15 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 227

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

For corners in

Lenawee
 (County)

Located In:

Corner Code #

18 DEC 97 10:27 A.M.

- | | | | |
|------------------------------------|-----------|-----------|-------|
| 1. Public Land Survey | T - 7 - S | R - 5 - E | A - 8 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec | S | T | R |
| | S | T | R |

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on December 15, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set on the G.L.O. survey
 Early 1900's J.L. Richard records "Old Stake"
 1967 I measured along the twp. line while trying to find M-8 T7S R4E and recorded the jog between the occupied lines to the East and West as 32.0'
 1986 Walter Frazier & Assoc. did a survey on the east side of Section 19 and used a point 0.50 chain (33') N. of the corner at M-8 T7S R4E
 J.L. Richard records give distance south to SW corner 2638.35 Measures 2639.29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 15, 1997 Dug through the pavement and set 3/4" X 3' iron pipe capped G.E.R. in monument box 36.48 feet north from M-8 T7S R4E being the location approved by the peer group on 10-28-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- "X" cut on face of 3 1/2" steel post S 75° E 18.21
- Survey mark spike & re-mon tag in 40" Oak S 5° E 232.10
- 12" boat spike 3' W. of pavement in drive S 25° W 39.71
- Telephone pedestal N 25° W 71.08
- 3/4" iron pipe in monument box @ M-8 T7S R4E South 36.48'



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date 12-18-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040