

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970 **LIBER 1 PAGE 213**

For corners in

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-7-S R-5-E	A-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED
17 OCT 97 3:56 P.M.
VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Glenn E. Richard, in a field survey on September 08, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher Intersect W. Bdg. 63 lks (41.58') N. of post. Set post at intersection cor. Sections 19 & 30 Elm 30 N 58 E 27 Sycamore 12 N 61 W 9
Did not find any information on this corner in either J. Blair or J.L. Richard's records
1955 Werner Sommer dug @ record jog and found old stake & tile "Set Hex iron"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1997 I found the Hex iron 0.17 West of the Twp. line between M-8 and M-9 T7S R4E. Removed the Hex and set a 3/4" X 3' iron pipe capped G.E.R. 0.17 East
Sept. 8, 1997 Set monument box. Len Co. Rd. Comm. layed new asphalt on 9-6-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E. R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & Len. co. Re-mon tag in E.P. N 15° E 124.10
- "X" cut on C.M.P. S 10° E 106.55
- "X" cut on C.M.P. S 10° W 101.95
- Found dbl hd nail & disc in 24" Mulberry S 30° W 30.17
- "X" cut on N. end C.M.P. N 15° W 87.43
- 3/4" iron pipe in monument box at M-9 T7S R4E South 41.33



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 30, 1997

Signed by Glenn E. Richard Date Oct. 7, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040