

SURVEY & REMONUMENTATION

FEB 16 1999

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 290
 STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

SECTION

10 DEC 1998 9:44:14 AM

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T -7 - S R - 5 - E	C - 2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 23, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher Set 1/4 Sec. post W. Oak 30 N 74 E 5 Beech 12 N 34 E 24
 1883 James Blair found a stone
 1919 J.L. Richard calls for 1/4 post. Didn't describe type of monumentation
 1974 Kenneth Suydam recorded the corner "Found iron pipe" and recorded it in Liber 4 P 151
 1989 I found the iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 23, 1998 Dug through new asphalt pavement and found 3/4" X 8" iron pipe over 1 1/4" X 24" iron pipe. Replaced the iron pipes with a 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

- Fd. dbl. hd. nail & disc in Elec. pole S 30° W 65.28
- Fd. P.K. nail in Elec. pole N 60° W 48.98
- Fd. nail & disc in face of 32" Maple N 35° E 54.84
- SW corner of house foundation N 50° E 111.49
- Survey mark spike and Len. Co. remon tag in Elec. pole S 70° W 70.08



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 19, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040