

**SURVEY & REMONUMENTATION**

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 291  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

10 DEC 1998 9:44:32 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 5 - E	C - 3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 23, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3		●											
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher Set post cor. Sec's 5, 6, 7 & 8 Beech 12 S 19 W 20 Beech 18 S 61 W 20  
 Early 1900's J.L. Richard. One record calls for stone and another for gas pipe  
 1974 Kenneth Suydam found a iron pipe & recorded it in L 4 P 151  
 1996 I found a re-rod in the pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 23, 1998, Dug through new asphalt pavement and found 1/2" X 8" re-rod over 3/4" X 21" galv. pipe. Replaced them with a 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 and set a monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

Fd. nail & washer in face of Elec. pole N 45° W 47.77  
 NE cor. of concrete porch S 55° W 109.26  
 Dbl. hd. nail & disc in Elec. pole S 10° W 164.99  
 Re-rod at R.O.W. intersection S 45° E 46.61



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040