

**SURVEY & REMONUMENTATION**

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIDER 1 PAGE 292

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

10 DEC 1998 9:45:07 AM

For corners in

Lenawee (County)	Located in:	Corner Code #
1. Public Land Survey	T-7-S R-5-E	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 27, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher Set 1/4 Sec. post Elm 20 S 52 W 15 B. Ash 6 S 89 W 7  
 Early 1900's J.L. Richard. One record calls for stake and another for iron 18" South of S. rail  
 1911 Charles Hoag, County Surveyor, "Found RR. iron about 1.5' from south rail"  
 1957 While surveying Blissfield Hwy from this corner to the south I dug and found piece of strap iron 1.6' South of south side of south rail of tracks 9'+ West of center line of pavement  
 1965 I dug and found a strap iron under piece of sand stone and raised to surface with iron pipe.  
 1981 I found the iron pipe and recorded it in L 5 P 19  
 1985 The road commission removed the R.R. tracks and removed the iron pipe. I set a 3/4" X 36" galv. pipe from the information given on my recording in L 5 P 19 and recorded it in L 5 P 152.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 27, 1998 Found 3/4" X 33" galv. pipe in pavement. Fd. piece of RR strap iron 18" deep leaning East with the top 0.15 East of location of galv. pipe. Replaced the galv. pipe with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod Lenawee County Remon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd. Dbl. hd. nail & disc in Elec. pole S 40° E 97.94
- Fd. Dbl. hd. nail & disc in Elec. pole S 15° W 79.67
- Fd. Dbl. hd. nail & disc in Elec. pole S 45° W 29.40
- Fd. P.K. nail in cable route post N 30° E 62.17
- Fd. "X" cut on CMP S 30° E 83.02



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040