

**SURVEY &  
REMONUMENTATION**

SEP 08 1996

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 102

For corners in  
Lenawee Located In: Corner Code #  
(County)

1. Public Land Survey T 7 - S R - 5 - E E - 1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**FILED**

11:37 AM

JUN - 4 1996

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 24 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher intersect N. Bdy. 48 links East of post. Set post at intersection corner Sections 4 & 5 Elm 14 N 84 E 11, B. Ash 10 N 54 W 14  
December 1884, James Blair did a survey of the NE 1/4 of Section 4 and shows the corner but didn't describe the monument.  
J.L. Richard records (early 1900's) shows the corner but doesn't describe the monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 24, 1995, I dug but didn't find anything. I set 30" Harrison monument stamped P.S. 13040 31.68 feet East of E-13, T6S-R5E on line to F-13, T6S-R5E. James Blair record East to F-1, T7S-R5E is 2658.48 feet, measures 2657.83 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
Dbl. hd. nail & disc in Elec. pole S 70° W 45.44  
Dbl. hd. nail & disc in 12' Cedar N 35° W 106.48  
"X" cut on North end C.M.P. N 55° W 49.80  
"X" cut on North end C.M.P. N 65° W 58.94  
"X" cut on South end C.M.P. S 75° W 87.68  
"X" cut on South end C.M.P. S 15° E 28.11  
E-13, T6S-R5E is West 31.68



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-18-95

Signed by Glenn E. Richard Date 1-15-96  
Glenn E. Richard

Surveyor's Michigan License No. 13040