

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Lenawee Located In: Corner Code #

- 1. Public Land Survey T-7-S R-5-E G-1
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec. S-T-R

4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on October 4 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher, intersect N. Bdy. 102 links (67.32) East of post. Set post at intersection corner Section 3 & 4 Elm 15 N 13 W 17, Maple 12 N 27 E 18 December 1884, James Blair found a stake 1.02 chain (67.32) East of G-13, T6S-R5E and added tile. May 1977, I set an iron pipe in the pavement 67.32 feet East of G-13, T6S-R5E on line to H-13, T6S-R5E and recorded it in Liber 3, Page 518

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 4, 1995, The pavement and the monument are both gone. Dug and found one small piece of tile. Set 30" Harrison Monument stamped P.S. 13040 67.32 feet East of G-13, T6S-R5E and on line between G-13 and H-13, T6S-R5E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner. SE. Corner of house foundation N 40° W 334.21 SW. Corner of house foundation N 50° W 94.88 Dbl. hd. nail & disc in Elec. pole N 25° W 168.73 Dbl. hd. nail & disc in 46" Maple S 55° E 29.34 G-13, T6S-R5E, West 67.32



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95

Signed by Glenn E. Richard Date 11-20-95

Surveyor's Michigan License No. 13040

FILED NOV 22 1995 LENAWEE COUNTY JEANETTE D. KNOX REGISTER OF DEEDS Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked in cell G-4.