

**SURVEY &
REMONUMENTATION**

SEP 03 1996

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 105

For corners in

Lenawee
(County)

Located In:

Corner Code #

1. Public Land Survey T-7-S R-5-E H-1
 T R
 T R
 T R
2. Property Controlling S T R
 in Section S T R
3. Miscellaneous S T R
 Property in Sec S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 5 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. This corner was not set on the original survey
 1907 J.L. Richard "Found stake in pike"
 May 1977, I found the wood stake and replaced it with a 3/4" iron pipe and recorded it in Liber 3, Page 518.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 5, 1996 I found the 3/4" iron pipe from the 1977 survey and replaced it with a 30" Harrison monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
 60 d spike in 30" Oak N 50 W 32.70
 Dbl. hd. nail & re-mon tag in 36" Ash N 85 W 250.26
 Angle iron fence corner post S 85 W 186.83
 S 1/4 corner Section 34, T6S R5E West 24.35

FILED 12:34 P.M.
 JUL 16 1996
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-12-95

Signed by Glenn E. Richard Date 6-21-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040

