

APR 6 1 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T-7-S R-5-E I-1  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

FILED

NOV 22 1995

11:52 AM

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Glenn E. Richard, in a field survey on October 18 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher intersect N. Bdy. 21 links East of post. Set post at intersection corner sections 2 & 3 W. Ash 10 S 27 E 19, Sugar 9 N 21 W 20  
 1907 J.L. Richard found stake, bricks & plow point. Set stake & tile on top.  
 October 1910, J.L. Richard found tile  
 May 1977, I found plow point brick & tile 1.14 South of town line and 13.86 East of I-13, T6S-R5E. Set 1/2" iron pipe on town line 13.86' East of I-13, T6S-R5E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 18, 1995, Found 1/2" iron pipe 13.86' East of I-13, T6S-R5E, Replaced it with a 30" Harrison monument stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
 SW. corner of conc. block house N 11° E 118.45  
 SE. corner of conc. block house N 24° E 127.61  
 SE. corner of garage N 35° E 160.51  
 "X" cut on face of 4" galv. post South 24.35  
 I-13 (SE. Cor. Sec. 34), T6S-R5E West 13.86



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10 - 19 - 95

Signed by Glenn E. Richard Date \_\_\_\_\_  
 Glenn E. Richard

Surveyor's Michigan License No. 13040