

**SURVEY & REMONUMENTATION**

Filed under Remonumentation Act 345 of 1990

NOV 07 1994

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 04

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 5 - E	J-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**FILED** 2:59 p.m.  
**OCT 10 1994**  
 LENAWEE COUNTY  
 JEANETTE C. KNOX  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on AUGUST 25 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher set post B. Ash 10 N 28E 24, B Oak 9 S 2 W 9 November 3, 1886, James Blair set stake and tile 98 3/8 links West of N 1/4 post of Section 2 midway between stake at SW corner and stake under a stone at the SE corner of Section 35, T8S-R5E. The corner monument couldn't be found during a survey of Stadler Road in 1958, and an axle was set at the record jog from the N 1/4 corner of Section 2, T8S-R5E. March 30, 1976, I found the axle shaft in a monument box and recorded it in L. 3, P. 394.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 25, 1994, Found axle shaft in Monument box 4" under present surface of pavement. Replaced the axle with 3/4" X 3' iron pipe capped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

Iron pipes North on 1/4 line 33.00 and 458.53  
 Dbl. hd. nail & disc in square post N 10° E 38.15  
 Dbl. hd. nail & disc in Elec. Pole S 65° E 139.99  
 Dbl. hd. nail & disc in Elec. Pole S 65° W 223.17  
 N 1/4 corner, section 2, T8S-R5E, East 64.83



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94  
 Signed by Glenn E. Richard Date OCT 10, 1994  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040