

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **05**

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7 S R 5 E Corner Code # K-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED
 OCT 10 1994 2:59 P.M.
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on Sept 23 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher set post Elm 9 S 40 W 5, Cottonwood 12 N 20 W 8 September 19, 1883, on a survey by James Blair "Corner stake found" November 3, 1886, James Blair called for stake under stone 14 links east of bridge. J.L. Richard records from early 1900's called for stone and stake. The bridge was there in 1958 during the road survey but the corner wasn't found and I set a 3/4" rod at the record jog west from the stone I found at the NE corner of Section 2, T8S-R5E. May 1972, Found iron and Werner Sommer recorded it in L. 1, P. 367. June 1984, dug and found the 3/4" rod and raised to surface with 1 1/4" X 9" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 29, 1994, Found the 1 1/4" iron pipe.
 Also found a 3/4" iron bar 4.96 N 70° 42' E (90° 00' sighting to S 1/4 corner, Sec 36, T7S-R5E).
 September 23, 1994, Replaced 1 1/4" iron pipe with 3/4" X 3' iron pipe in monumnet box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped 13040 in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

NW corner of SW wingwall of original bridge (only one left) S 70° W 29.40
 "X" cut on C.M.P. N 10° W 33.38
 "X" cut on C.M.P. S 60° E 44.95
 NW corner of house found. S 60° E 158.19
 Dbf. hd. nail & disc in base of old Elec Pole N 70° E 103.49
 NE corner of Section 2, T8S-R5E, East 75.15



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94
 Signed by Glenn E. Richard Date October 3, 1994
 Surveyor's Michigan License No. 13040