

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

NOV 07 1994

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 06

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>7-S</u> R <u>5-E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

OCT 10 1994

2:59 p.m.

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 29 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher set post W Ash 10 S 32 E 18, Cottonwood 16 N 22 W 20 September 19, 1883, Survey by James Blair states he re-established the corner midway between SW and SE corners of Section 36, and placed 2 stones.
J.L. Richard records called for stake and stone.
May 16, 1972, We dug and found a square stone 38' West of stone we found at the N 1/4 corner of Section 1, T8S-R5E. Set iron pipe on west side of stone and bent top over center of stone, and Werner Sommer recorded it in L. 1, P 371.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 29, 1994, Found iron pipe.
September 30, 1994, Found stone 12" deep. Drilled through stone and bit became wedged on another stone. Couldn't remove it without digging larger hole in pavement, so left it and capped P.S. 13040, and placed monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 16" carbide bit capped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Dbl. hd. nail & disc in square post N 50° E 29.89
- Dbl. hd. nail & disc in Elec Pole N 85° E 194.89
- Dbl. hd. nail & disc in Elec Pole S 80° E 175.21
- Dbl. hd. nail & disc in Elec Pole S 80° W 184.26
- SW cor house found. N 70° E 230.40
- N 1/4 corner Sec 1, T8S-R5E, East 38.01



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-15-94

Signed by Glenn E. Richard Date Oct 10, 1994

Glenn E. Richard

Surveyor's Michigan License No. 13040