

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - 8 - S R - 1 - E	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**FILED**  
**OCT 09 1995**  
 LENAWEE COUNTY  
 JEANETTE D. KNOX  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 20, 1824 Ziba Swan set post com. Sec 17, 18, 19 and 20 W. Oak 20 S 42° W 23 W. Oak 11 N 54° W 29 1918 J.L. Richard surveyed Munson Hwy. Didn't find anything "Drove gas pipe" 1927 H. Clegg witnessed the corner but didn't describe the monument May 1976 All of above witnesses were gone. We dug and found piece of square iron, bricks, wood stake and added 3/4" X 2' iron pipe and recorded it in Liber 3, Page 419

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 15, 1995 Found the 3/4" X 2' iron pipe in monument box which checked the remaining witnesses. Replaced the iron pipe with a 3/4" X 3' gas pipe capped G.E.R. P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 Northeast corner of concrete headwall N 20° E 54.06  
 Southwest corner of concrete headwall N 20° W 48.32  
 Southwest corner of concrete headwall S 70° W 34.53  
 "X" cut on top of catch basin set in concrete N 75° E 53.25  
 Dbl hd nail and disc in 24" Maple S 80° E 154.58  
 The corner is 1.5 ± West of Munson Hwy center line and 1.5 South of Lime Creek Rd. centerline.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 18, 1995.

Signed by Glenn E. Richard Date 9-28-95  
 Glenn E. Richard

Surveyor's Michigan License No. 13040