

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8 - S R - 1 - E	C-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

OCT 09 1995

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	34	32	33	34	35	36						
13												

I, Glenn E. Richard, in a field survey on July 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 20, 1824 Ziba Swan set post com. Sec. 19, 20, 29 and 30 W. Oak 10 S 88° E 6 W. Oak 7 S 5° W 15 1918 ± J.L. Richard surveyed Munson Hwy " Found corner stones and bricks. Drove gas pipe" U.S.G.S. B.M. Southwest 38.5
 May 1966 I dug and found the iron pipe 24" deep and raised with iron pipe U.S.G.S. B.M. Southwest 38.64
 May 1993 W. Sommer found the iron pipe and recorded it in Liber 4, Page 386.
 October 1993 W.E.F. and assoc. replaced the iron pipe with a re-rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 12, 1995 Found re-rod under first course of new asphalt pavement capped W.E.F. which checked my witnesses of May 1993. Replaced the re-rod with 3/4" X 2' gas pipe (over original iron pipe) and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 2' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 U.S.G.S. B.M. S 45° W 38.68
 Southeast corner of house foundation N 20° W 292.26
 Dbl hd nail and disc in E.P. S 60° E 55.43
 Dbl hd nail and disc in 12" Hickory S 15° W 90.02
 60 g spike on section line East 130.71
 1/4 corner East 2662.17
 1/4 corner North 2801.80
 1/4 corner South 2662.15
 The corner is 7' West of the pavement centerline.

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-18-95

Signed by Glenn E. Richard Date 9-28-95
 Glenn E. Richard

Surveyor's Michigan License No. 13040

