

NOV 09 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

FILED

OCT 09 1995

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Lenawee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T-8-S R-1-E C-10  
 T. \_\_\_\_\_ R. \_\_\_\_\_  
 T. \_\_\_\_\_ R. \_\_\_\_\_  
 T. \_\_\_\_\_ R. \_\_\_\_\_

2. Property Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 Property in Sec. S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on July 12 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G.L.O. March 20, 1824 Ziba Swan set post W. Oak 14 N 40° E 52 B. Ash 12 N 10° W 40  
 1918 ± J.L. Richard surveyed Munson Hwy. "0 + 00 = W 1/4 post Section 29-8-1"  
 Def. 0° 22' L from gravel pike South "(No description of type of monument or if found or set)  
 November 1983, K.L. Suydam Found iron pipe and recorded it in Liber 5, Page 108  
 (All witnesses gone in 1993)  
 May 1993, I dug through the pavement and found a 1/2" X 22" galv. pipe and replaced it with  
 a 3/4" X 3' gas pipe capped G.E.R. P.S. 13040

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 12, 1995 found 3/4" gas pipe under first course of new asphalt pavement and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 "X" cut on North end C.M.P. S 70° E 24.56  
 "X" cut on South end C.M.P. S 30° E 50.51  
 Set 1/2" re-rod West 28.50  
 Center of telephone pedestal N 85° W 29.15  
 Center of telephone pedestal S 85° W 28.20  
 The corner is 2' West of the pavement center line.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Dated September 18, 1995.

Signed by Glenn E. Richard Date 9-28-95  
 Glenn E. Richard

Surveyor's Michigan License No. 13040