

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1

PAGE 350

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

15 NOV 1999 9:53:09 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

1. Public Land Survey	T	8-S	R	2-E	D-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on November 4, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1824 Ziba Swan set 1/4 Sec. post W. Oak 30 N 30° E 68 Maple 14 N 65 W 55
- 1873 James Blair did survey for Coomer St. and calls for the corner but not type of monumentation
- 1882 James Blair surveyed Fay Hwy. and used the corner. Type of monumentation not given
- 1936 Walter Frazier shows the corner on Assessor's Plat No. 2 of Morenci. Type of monumentation not given
- 1975 I dug and found gas pipe in the subsoil and raised to the surface with re-rod
- 1999 I found re-rod 4" deep and raised with spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Oct. 20, 1999 Dug in subsoil after the pavement had been removed during road construction. All traces of the monumentation was gone.
- November 4, 1999 Set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 at location of found iron pipe prior to road construction. Set monument box in new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Plat monument S 70° W 95.95
- Survey mark spike and Lenawee County re-mon tag in E. P. S 55° W 40.03
- M. Bartolo capped iron over plat monument S 35° E 42.55
- SE corner of house foundation N 35° W 105.85
- NW corner of house foundation S 25° W 142.18

D-1 T9S R2E East 25.08



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Nov. 9, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040