

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE** LIBER 1  
 Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 351  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

JAN 25 2000

For corners in SECTION  
Lenawee  
 (County)

Located In:	Corner Code #
T - 8-S R - 2 - E	E-13
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	

15 NOV 1999 9:53:30 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec
- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1824 Ziba Swan set 1/4 Sec. post W. Oak 30 N 30° E 68 Maple 14 N 65 W 55
- 1874 James Blair found corner. Bearing trees W. Oak 18 N 22 E 67 Hickory 12 N 35 W 58 1/2 (38.61')
- 1874 The corner is labeled as stone on Blairs survey in the Co. Surveyor book
- 1915 J.L. Richard found stone & put bricks on top. Hickory still standing.
- 1956± I dug and found stone, bricks & wood stake. Raised with 3/4" iron bar. South corner of concrete headwall NE 30.15. South corner of concrete headwall NW 30.15
- 1973 The iron bar was gone, dug & found stone & bricks and set a iron pipe at the surface at the record distances from concrete headwalls
- 1975 I found the iron pipe and recorded it in Liber 3, Page 367

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 17, 1999 Found 3/4" X 20" iron pipe & bricks over stone. Drilled thru stone & drove 5/8" X 3' re-rod thru the hole and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- NE corner of concrete head wall N 55° E 30.86
- Fd. dbl. hd. nail in E.P. S 60° E 46.70
- N.W. corner of house foundation #8977 S 35° E 139.53
- dbl hd nail & re-mon tag in E.P. S 80° W 141.73
- E-1 T9S R2E East 9.24 (3/4" iron pipe in the pavement)



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999  
 Signed by Glenn E. Richard Date Nov. 9, 1999  
 Surveyor's Michigan License No. 13040