

APR 01 1996

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 75

COMMISSION

FILED

12:09 P.M.

NOV 21 1995

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T-8-S R-2-E G-6
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on December 15 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 1824, John Mullett set 1/4 Sec. post W. Ash 8 N 77 E 15, W. Oak S 36 1/2 W 11.
May 1878, James Blair did a survey for the Seneca Township Highway Commissioner from the North "S 3° 10' E 40.05 to 1/4 post. Set new stake."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

December 15, 1994, We re-traced the Blair survey using the line from the W 1/4 corner of Section 22 to the NW corner of Section 15 and the S1/4 corner of Section 15 and the S 1/4 corner of Section 16. We dug through the pavement and at 2' deep found an old scythe blade, bricks in remains of old wood stake (soft spot and Void areas). The corner is 4' East of the west edge of the pavement.
September 25, 1995, Set 3/4" X 3' gas pipe in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Dbl. hd. nail & disc in:
Elec. pole N 5° E 403.51
Elec. pole S 85° E 22.50
Elec. pole S 5° E 29.53
West side of concrete headwall at wall deflection near North end S 5° W 116.55
Section corner South 2646.09
Section corner North 2647.35

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-18-95

Signed by Glenn E. Richard Date 10-9-95
Glenn E. Richard

Surveyor's Michigan License No. 13040

