

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 64

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

DEC 29 1994 3:51 P.M.

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8 - S R - 2 - E	<u>K - 4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 26 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 1824, John Mullett set 1/4 sec. post, B. Oak 30 S 45 W 28, W. Ash 8 N 40 E 27
J.L. Richard records from the early 1900's called for stones.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 25, 1994, Dug hole 10'± square with back hoe and found 6"X8"X18" stone surrounded by bricks and smaller stones. Set 30" Harrison monument and laid stone flat next to the monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
Dbl. hd. nail & disc in Elec. pole S 65° E 57.96
Dbl. hd. nail & disc in post S 5° E 18.39
Dbl. hd. nail & disc in Elec. pole S 85° W 319.09
Fd. iron pipe N 5° E 24.23 (I set this 1-16-69 in base of old post).
Fd. iron pipe at Center of Section 12, T8S-R2E, East 2644.05



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 22, 1994
Signed by Glenn E. Richard Date Dec 23, 1994
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983