

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE **FIBER 1** PAGE **193**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-8-S R-2-E L-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec S T R

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

9 OCT 97 3:39 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on Sept. 3, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mullett set 1/4 sec post Beech 14 S 43 E 27 Beech 24 S 45 W 48
1886 James Blair found stake & added tile. The corner is 6 links south of a straight line.
January 1973 I retraced the south line of the above survey and set a P.K. nail in the pavement for the corner & recorded it in L 2, P 313.
Jan 1991 I found a R.R. spike but it didn't check to the recorded location as it was 0.9' too far west.
Jan 1992 Werner Sommer surveyed the SE 1/4 of Sec 13 and used the recorded location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 12, 1997 Found R.R. spike in monument box. Retraced my 1973 survey when I re-established the corner and it falls 0.90 East of the found R.R. spike.
Sept. 3, 1997, I dug the monument box out of the pavement and moved it 0.9 +/- East and set a 3/4" X 3' iron pipe capped G.E.R. 13040 in the monument box at the location recorded in L 2, P 313.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe in monument box capped G.E.R. 13040 and is accepted as the best available evidence of the position of the original corner.
"X" cut on top of N. end concert culvert N 75° W 111.10
"X" cut on top of S. end concert culvert S 75° W 110.73
dbl. hd. nail & disc in 6" Elm S 25° W 47.15
F.I.P. capped G.E.R. North 32.92



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040