

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990 LIBER 1 PAGE 228

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

22 DEC 97 9:23 A.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8 - S R - 2 - E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on December 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824 Ziba Swan Set 1/4 section post Hick 16 S 12 1/2 W 19 Beech 26 N 15 1/2 E 23
- 1871 Burton Kent "found 1/4 post to correspond with the witness trees, the stumps of which were found standing"
- 1880 James Blair "Found 1/4 post"
- 1918 J. L. Richard RLS No. 171 records call for "stone found"
- 1972 Tim Mohr under my direction dug and found large stone 1.5 deep and raised with 3/4" X 4' iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 11, 1997 Found 3/4" X 3' iron pipe on west side of 4" X 5" X 22" square cut stone
Dug out the iron pipe & stone and set 30" Harrison monument at location of iron pipe and reset the stone along the east side of the harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Found dbl. hd. nail in E.P. N 80° E 112.74
- Found dbl. hd. nail & disc in fence post South 24.17
- Survey mark spike & re-mon disc in 4" Oak S 5° W 34.91
- Survey mark spike & re-mon disc in 8" Basswood
- Dbl. hd. nail & disc in E.P. N 80° W 167.14



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
Glenn E. Richard

Surveyor's Michigan License No. 13040