

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 42

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey T-8-S R-2-E M-5  
 T R  
 T R  
 T R
2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on November 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 1824, John Mullett set post corner Sections 12 & 13, Ironwood 5 S 14 W 14, W. Oak 8 S 42 W 24.  
 April 1886, James Blair re-established the corner with stake and bricks by running a straight line between the found E. 1/4 corner of Section 13, T8S-R2E (Blair treated as a common corner with the W 1/4 corner of Section 18, T8S-R3E) found NE. corner of Section 12, T8S-R2E.  
 April 1940, Harold Clegg, R.L.S. 13578, found the corner (no description) and set iron pipe 33' from the centerlines NE., SE., SW. & NW.  
 February 8, 1969, I dug and found strap iron 2' under the pavement and raised with iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 8, 1994, Dug and found iron pipe 8" deep under new asphalt pavement which checked my witnesses from 1969 and witnesses shown on a survey by K.L. Suydam and recorded in L. 1 of Surveys, P. 297. Removed the found iron pipe and set 3/4" X 3' iron pipe capped G.E.R. P.S. 13040 in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe in monument box capped G.E.R., P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
 Fd. nail & disc in Elec. pole S 45° E 30.60  
 Fd. nail & disc in Elec. pole N 25° W 53.55  
 Fd. nail & disc in guy pole N 35° E 36.80  
 Found iron pipe 15" deep N 45° W 46.72  
 Dbl. hd. nail & disc in Elec. pole S 85° E 284.21  
 Cut "X" on C.M.P. S 30° E 29.60  
 Cut "X" on C.M.P. S 30° W 29.11

**FILED**

DEC 05 1994 2:01 P.M.

LENAWEE COUNTY  
JEANETTE D. NOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345  
 Signed by Glenn E. Richard  
 Glenn E. Richard

Co. Rep. Glenn E. Richard Date November 17, 1994  
 Date Nov. 29, 1994

Surveyor's Michigan License No. 13040

