

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 DIBER 1 PAGE 194

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 2 - E	M-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

9 OCT 97 3:40 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on June 13, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mullett D.S. Beech 9 cor Sec 13 & 24
 1886 James Blair found stone - set iron & tile
 J.L. Richard records are same as Blair's
 1962 I set a drag tooth in the pavement 15.84 (24lks per GLO) north of A-7 T8S-R3E
 1975 I found the drag tooth and recorded it in L3 P348
 1993 The road was reconstructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 12, 1997 Found drag tooth tipped over in monument box
 June 13, 1997 I dug and probed in monument box but found nothing else. Retraced survey done 10-8-1975 to verify location as recorded in L 3 P348 and set 3/4" X 3' iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Found dbl. hd. nail & disc in E.P. N 45° W 32.27
 Found dbl. hd. nail & disc in E.P. N 10° W 197.20
 Found dbl. hd. nail & disc in E.P. N 70° E 49.55
 Telephone pedestal S 30° W 47.61
 3/4" X 3' iron pipe in monument box at A-7 T8S R3E South 15.84



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept. 19, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040