

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 327
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

1 SEP 1999 5:42:27 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 8 - S R - 2 - E	M-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on August 17, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1824 John Mullett set 1/4 post Hickory 6 N 37 W 8 Ironwood 2 S 9 W 13
1922 J.L. Richard surveyed Terry Hwy. found stone End post N 83° 45 W 21.0' line fence west is 2.7 to far to the north
March 1, 1998 I dug with a back hoe. Found only two small stones.
March 3, 1998 I retraced the 1922 road survey and set a 3/4" X 3' Iron pipe surrounded by 8" diameter stones.
The corner is 5.88 West of line between the Section corners

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 17, 1999 Replaced the Iron pipe with a 30" Harrison Monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison Monument with Lenawee County Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

Dbl hd nail & disc in square wood end post N 85° W 19.93
Cut "X" on N. end C.M.P. S 70° W 13.12
Cut "X" on S. end C.M.P. S 25° W 26.87
SE corner of Section 36 South 2642.17
NE corner of Section 36 North 2650.86



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040