

JAN 15 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee (County)	Located in:	Corner Code #
1. Public Land Survey	T - 8 - S R - 2 - E	M-13
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

LIBER 1 PAGE 329
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

1 SEP 1999 5:42:51 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on August 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1824 GLO John Mullett intersect W. bdg. 710 lks S of temp post set post at intersection corner T 8 & 9 S R 2 & 3 E Maple 18 N 62 E 32 W. Ash 12 N 44 W 48
- 1874 James Blair found stake and stone
- 1916 J.L. Richard records call for large stone. Fence post N.E. 30.5 End post South 25.7
- 1922 J.L. Richard surveyed Yankee Road across the south side of Sections 31 & 32 T8S R3E Notes call for SW corner Sec. 31 (type of monumentation not given) NW corner of house S 32 E 128.2' Hickory S 68° 30' W 81.8 Fence post N 45° 30' E 30.7'
- 1972 Kenneth Suydam retraced the 1922 road survey and set a iron pipe NW corner of house S 32 E 128.2' E.P. N 45 E 32.62' E.P. S 45 E 50.77'
- 1989 I found iron pipe in the pavement
- 1991 I found iron pipe in the pavement
- 1998 Found iron pipe in the pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 17, 1999 I replaced the iron pipe with a 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

- NW corner of house S 32° E 128.27
- Fd. nail & disc in face of E.P. N 45° E 32.66
- Fd. nail & disc in face of E.P. S 55° E 50.83
- Face of steel post in concrete South 26.93

2'± North of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999
Signed by Glenn E. Richard Date Aug. 23, 1999
Surveyor's Michigan License No. 13040