

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 198

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey

T-8-S R-3-E

A-7

T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

2. Property Controlling in Section

3. Miscellaneous Property in Sec

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

9 OCT 97 3:41 P.M.

Register of Deeds Stamp & File Number  
VICTORIA J. DANIELS  
REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 13, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mullett Intersect W. Boundary 24 lks. S. of post, Sugar 12, cor. Section 18 & 19 1880's record of James Blair called for iron.  
Early 1900's J.L. Richard records called for iron.  
1961, I dug and found iron (plow point) & raised to surface with an iron pipe.  
10-8-1975 I found the iron pipe while doing a survey in Sec. 24 T8S R2E  
1981, I found the iron pipe and recorded it in L. 5, P. 24.  
1993 The road was reconstructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 12, 1997 Found split seam iron as set in 1961 in monument box.  
June 13, 1997 Retraced survey done 10-8-1975 to verify location as recorded in L 5, P 24 which in on line between M-7 and M-8 T8S R2E. Replaced the found split seam iron with 3/4" X 3' iron pipe capped G.E.R. 13040 and hit something when setting the 3' iron pipe. I bent it so the top is at the location of 10-8-1975.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Found dbl. hd. nail & disc in E.P. N 30° W 44.74  
Found dbl. hd. nail & disc in E.P. N 5° W 212.95  
Found dbl. hd. nail & disc in E.P. N 55° E 57.31  
Telephone pedestal S 45° W 34.91  
3/4" X 3' iron pipe in monument box at M-7 T8S R2E North 15.84

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997  
Glenn E. Richard

Surveyor's Michigan License No. 13040