

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 41

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-8-S R-3-E B-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED

DEC 05 1994 2:01 P.M.

LENAWEE COUNTY
JEANETTE D. INOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5	●													
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on November 8, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. March 1824, John Mullett set 1/4 sec. post B. Oak 16 N 3 W 26, B. Oak 14 S 2 E 34.
 April 1886, James Blair found corner - stone pump and bricks.
 April 1940, Harold Clegg, found corner, Set Irons 33' North and 33' south.
 August 4, 1969, I dug and found boat spike over stone pump and galv. pipe 33' North and replaced the spike with iron pipe and set in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 8, 1994, Dug and found Iron pipe in monument box (no top) 8" deep under three layers of asphalt. Replaced iron pipe with 3/4" X 3" iron pipe capped G.E.R., P.S. 13040 and used three adjusting rings to bring up to surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped G.E.R., P.S. 13040, in monument box and is accepted as the best available evidence of the position of the original corner.
 Found iron pipe North 33.00
 Dbl. hd. nail & disc in Elec pole S 85° W 225.27
 Dbl. hd. nail & disc in Elec. pole S 80° E 112.09
 Cut "X" on east end field tile Outlet C.M.P. S 5° W 238.79



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 17, 1994
 Signed by Glenn E. Richard Date Nov. 25, 1994
 Surveyor's Michigan License No. 13040