

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 199

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8-S</u> R <u>3-E</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

9 OCT 97 3:41 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mullett set 1/4 Sec. post Sugar 10 N 69 E 38, W. Ash 6 S 26 W 30  
Couldn't find any record of this corner in James Blair's or J.L. Richard records.  
1986 I found a R. R. Spike  
1988, Survey by K.L. Suydam recorded it in L. 1083, P. 913 noted "Found iron"  
1990, Mannik & Smith Engineers found R.R. Spike.  
1993, Road was re-constructed.  
Aug 1993 I found a empty monument box. Dug 3' deep in box & probed but didn't find anything else.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 11, 1997 Found a empty monument box. I retraced K.L. Suydam's survey and set a 3/4" X 3' gas pipe capped GER 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped GER 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
Re-mon tag & survey marker spike in E.P. S 70° E 89.10  
NE corner of hse # 4495 foundation S 30° E 86.26  
NW corner of hse # 4495 foundation S 10° E 75.08  
iron pipe south 33.00  
iron pipe south 165.00



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997  
Glenn E. Richard

Surveyor's Michigan License No. 13040