

**SURVEY & REMONUMENTATION**

**JAN 15 1998**

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 222

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

Lenawee  
(County)

Located in:

Corner Code #

- |                                    |       |       |     |
|------------------------------------|-------|-------|-----|
| 1. Public Land Survey              | T-8-S | R-3-E | E-7 |
|                                    | T     | R     |     |
|                                    | T     | R     |     |
|                                    | T     | R     |     |
| 2. Property Controlling in Section | S     | T     | R   |
|                                    | S     | T     | R   |
| 3. Miscellaneous Property in Sec   | S     | T     | R   |
|                                    | S     | T     | R   |

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

5 NOV 97 11:57 A.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on February 12, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. 1824, John Mullett set post cor. Sec. 16, 17, 20 & 21 Hickory 8 S 14 E 22 Sugar 6 N 46 W 22  
 March 1908 J.L. Richard "said to be stone could not find it."  
 1915 J.L. Richard surveyed Lyons Hwy to south. Station 0 + 00 at section corner common to Sections 16, 17, 20 and 21. Gas pipe at Section corner.  
 1970 Associated Engineers & Surveyors found iron pipe  
 1979 I found iron pipe and recorded it in L 4, P 256  
 1984 Walter E. Frazier Found iron pipe  
 1991 Mannik & Smith Engineers found iron pipe  
 1993 The road was re constructed

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Feb. 12, 1997 I found 3/4" iron pipe in monument box which checked W.E.F. & Assoc. recorded angle at the NW corner of Section 21 and the distances East and South.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Capped existing 3/4" iron pipe GER 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Survey mark spike & re-mon tag in E.P. N 80° W 204.18  
 NE corner of house foundation N 40° W 158.06  
 SE corner of house stone foundation N 50° W 126.42  
 SW corner of house stone foundation N 55° W 146.43  
 NE corner of house foundation S 45° W 104.05  
 Found dbl. hd. nail & disc in E.P. S 55° E 89.30



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997  
 Glenn E. Richard

Surveyor's Michigan License No. 13040