

**SURVEY & REMONUMENTATION**

**JAN 15 1998**

**SECTION**

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 223

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee  
(County)

Located In:

Corner Code #

- |                                    |           |           |       |
|------------------------------------|-----------|-----------|-------|
| 1. Public Land Survey              | T - 8 - S | R - 3 - E | F - 7 |
|                                    | T         | R         |       |
|                                    | T         | R         |       |
|                                    | T         | R         |       |
| 2. Property Controlling in Section | S         | T         | R     |
|                                    | S         | T         | R     |
| 3. Miscellaneous Property in Sec   | S         | T         | R     |
|                                    | S         | T         | R     |

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

5 NOV 97 11:58 A.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1824 John Mullett Hickory 7 for 1/4 Sec. corner
- May 1908 J. L. Richard "Planted stake. Stone on top"
- 1977 K.L. Suydam found drive shaft and recorded it in L 3, P 455
- 1984 Walter E. Frazier and Assoc. found axle shaft
- 1991 Mannik & Smith Engineers found 1" bolt
- 1993 The road was re constructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Feb. 7, 1997 I found drive shaft in monument box which checked W.E.F. & Assoc. record angle at the NW corner of Section 21 and distance to NW corner.
- Oct. 23, 1997 Attached re-mon tag stamped G.E.R. PS 13040 to existing drive shaft in monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-mon witness tag stamped G.E.R. PS 13040 on top of existing drive shaft in monument box and is accepted as the best available evidence of the position of the original corner.

- Cut "X" in C.M.P. S 55° E 64.90
- Cut "X" in C.M.P. S 5° E 37.54
- Survey mark spike & re-mon tag in E.P. N 5° E 213.41
- NW corner of telephone pedestal N 75° E 121.31



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997  
Glenn E. Richard

Surveyor's Michigan License No. 13040