

**SURVEY & REMONUMENTATION**

**JAN 15 1998**

**SECTION**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 224  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in			
<u>Lenawee</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T - <u>8-S</u> R - <u>3-E</u>	<u>G-7</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

5 NOV 97 11:58 A.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1824 John Mullett set post corner Sections 15, 16, 21 & 22 Beech 8 N 51W 4 Beech 12 S 53 E 29
- 1908 J.L. Richard Found large stone 2' across
- 1957 +/- W.E. Sommer set spike from "appr. remains of witnesses"
- 1966 I found the R. R. spike
- 1982 Don Olmstead recorded the corner in Liber 5 Page 46 "Found R. R. spike"
- 1991 Mannik & Smith Engineers found 5/8" iron rod
- 1993 The road was reconstructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 3, 1997 I found a 3/4" iron pipe in a monument box which checked my 1966 angle in the SE corner of Section 16 and the angle and distance to the iron pipe I drove 33' N and 33' W of section lines.  
 Oct. 23, 1997 Probed for stone but didn't find any. Capped existing iron pipe G.E.R. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Found iron pipe N 45° W 47.01
- Found P.K. nail & disc in W. face E.P. N 15° E 103.79
- Found P.K. nail & disc in S. face E.P. N 15° E 103.45
- Found P.K. nail & disc in S. face E.P. N 20° E 76.56
- dbl hd nail & disc in 22" Hickory S 70° E 107.22
- dbl hd nail & disc in E.P. S 10° E 162.80



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997  
 Glenn E. Richard

Surveyor's Michigan License No. 13040