

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 225

For corners in **SECTION**

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T-8-S R-3-E	H-7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

5 NOV 97 11:58 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7				●										
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on October 23, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1824 John Mullett set 1/4 sec post Sugar 5 S 82 E 14 Sugar 7 N 58 W 23
- 1886 James Blair Found the corner "stake and bricks" and set stone pump.
- Early 1900's J.L. Richard records same as J. Blairs
- 1956 MSHD found 1 1/4" iron pipe
- 1968 I found the 1 1/4" iron pipe
- 1988 W.E. Frazier & Assoc. found 2" iron pipe
- 1990 I found the 1 1/4" iron pipe
- 1991 Mannik & Smith Engineers found 2" iron pipe
- 1993 The road was reconstructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 23, 1997 Found 1 1/4" X 17" iron pipe in monument box. Dug inside of box. Probed and hit something on east side of box 3 1/2' deep but couldn't dig that deep.
 It checks A.E.S. 1989 distance east to S.E. corner and distance west to S.W. corner of Section 15
 Set 3/4" X 3' iron pipe capped G.E.R. 13040 in location of the found iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. in monument box and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & re-mon tag in W. face E.P. North 67.43
- Found P.K. nail & disc in S. face of E.P. North 66.98
- Cut "X" on W. end C.M.P. N 55 W 44.35
- Cut "X" on W. end C.M.P. S 10° W 27.33
- Cut "X" on E. end C.M.P. S 50° E 40.43



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040