

**SURVEY & REMONUMENTATION**

**JAN 15 1998**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 226  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T - <u>8-S</u> R - <u>3-E</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

5 NOV 97 11:59 A.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 23, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1824 John Mullett set post corner Sections 14, 15, 22 & 23 Sugar 12 514 E 24 Beech 8 N 65 W 390  
 1886 James Blair Searched for corner but couldn't find. Re-established it by proportional distances from 1/4 corners found 1/2 mile N, E, S & W. Set stone pump.  
 Early 1900's J. L. Richard records same as J. Blair.  
 1956 M. S. H. D. found iron pipe.  
 1968 I found 1" steel bar in monument box.  
 1973 K. L. Suydam recorded the corner as F I P in monument box in Liber 4 Page 115.  
 1978 K. L. Suydam recorded the corner as F I P in monument box in Liber 4 Page 183.  
 1991 Mannik & Smith Engineers found "Concrete monument ? "

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Oct. 23, 1997 Found boat spike in monument box. Probed and hit something 2 1/2" deep. Dug but it was small pieces of lime stone. Found traces of brick in the clay. Set 3/4" X 3' iron pipe capped G.E.R. 13040 in location of the boat spike.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Angle iron post in concrete N 20° W 202.23  
 Fd PK & M.S.H.D. tag in E. P. N 25° E 174.11  
 "X" cut on top conc. culv. N 65° E 72.57  
 "X" cut on top conc. culv. S 65° W 72.53  
 "X" cut on top conc. Hdwl S 65° W 63.15  
 "X" cut on top conc. Hdwl N 65° W 64.15



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997  
 Glenn E. Richard

Surveyor's Michigan License No. 13040