

**SURVEY & REMONUMENTATION**

**JAN 15 1998**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 **1** PAGE **214**

**SECTION**

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - <u>8-S</u> R - <u>3-E</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

17 OCT 97 3:56 P.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 30, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**\*NOTE: SEE COMMENTS & SKETCH ON BACK**

G.L.O. 1824 John Mullett ran a corrected town line from the south and set post corner Sections 1 & 12 5.26 chains North of the old Section corner by Joseph Wampler W. Oak 18 S 50 W 42 Lynn 7 N 26 W 13  
 1920 J.L. Richard records show witnesses (all gone) to S.E. corner Section 1 and don't describe type of monumentation  
 1970 Werner Sommer re-established the corner at record jog north from A-3 T8S R4E on line extended north from M-4 T7S R3E and recorded it in L 1, P 625

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 30, 1997 The pavement had been scarified. I found the bottom of the 3/4" iron pipe set by Werner Sommer. I dug and probed deeper and wider but didn't find anything else. Replaced the found iron with a 3/4" X 3" iron pipe.  
 Oct. 8, 1997 Set monument box in base course of new asphalt pavement

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped G.E.R. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.  
 "X" cut on S. end CMP S 50° W 31.77  
 "X" cut on N. end CMP N 50° E 34.52  
 Survey mark spike & re-mon tag in E.P. N 10° E 167.34  
 Found dbl. hd. nail & disc in E.P. S 10° E 160.29  
 Iron pipe in monument box at A-3 T8S R4E South 297.66



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Oct. 14, 1997  
 Glenn E. Richard

Surveyor's Michigan License No. 13040