SURVEY & REMONUMENTATION

JAN 1 5 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATEBER 1 PAGE 216

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Lenawee (County)	Located In:	Corner Code #	STATE OF NICHIGAN LENAWEE COUNTY FILED
1. Public Land Survey	T <u>-8-S</u> R <u>-4-E</u> T R	A-3	17 OCT 97 3:57 P.M. VICTORIA J. DANIELS
2. Property Controlling S_in Section S_3. Miscellaneous S_	T R R T R T R R T R R T R R T R R T R R T R R T R R T		REGISTER OF DEEDS Register of Deeds Stamp & File Number
Property in Sec S_ 4. Lot No, Reco	TR_		A B C D E F G H I J K L N
5. Private Claims			3 4 7 8 9 10 11 12
I. Glenn E. Richard , in a field survey on October 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below: NOTE: Not more than 4 corners, all in the same town and range, may be recorded		d 6 48 47 6 15 44 13 d 7 5 8 49 20 21 22 23 24 a	
		10 30 29 28 27 26 25	
on this certificate.		in and range, may be recorded and range, may be recorded and/or subsequent restoration:	12 31 32 33 34 35 36 13
		•	

*NOTE: SEE COMMENTS & SKETCH ON BACK

G.L.O. 1820 Joseph Wampler intersect W. Bdg. 75 lks N. of post. Set post at intersection cor. Sec. 6 & 7 Elm 14 S 18° W 27 Lynn 10 S 68° E 25

Early 1900's J. L. Richard record's call for "Gas pipe & bricks"

1962 K.L. Suydam "Found iron pipe and bricks & raised with 3/8 "iron pipe"

1995 I found the road under re-construction and the iron pipe. Set re-rod over the iron pipe.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 8, 1997. Found re-rod under base course of new asphalt pavement. Drove 3/4" X 3' iron pipe capped G.E.R. 13040 over re-rod and set monument box. It is 297.66 South of M-3 T8S R3E and on line between M-3 and M-4 T8S R3E.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

dbl. hd. nail & disc in guard rail post West 11.49

dbl. hd. nail & disc in E.P. N 10° E 140.88

dbl. hd. nail & disc in E.P. N 70° E 77.22

dbl. hd. nail & disc in E.P. S 15° E 114.62

3/4" iron pipe in monument box at M-3 T8S R3E North 297.66

SHARE OF MICHAELE SALE OF MICHIGA GLENN E. RICHARD No. 13040 SONAL SU AND THE PROPERTY OF

Ratified by Peer Group in accordance with P.A. 345	Co. Rep. Dlenn Etukard. Date Sept. 30, 1997	
SIA DADA	1 0 ± 1/1 100=	

Glenn E. Richard

Date (207. 14,197)

COMMENTS: The G.L.O. Plat maps for T8S-R3E and T8S-R4E are in conflict as to the jogs of the section lines.

1819, Joseph Wampler surveyed the township line from North to South, apparently making an error of approximately 5 chains as he shows the last distance to be 96.15 chains and corrected all temporary corners 16.15 chains South.

1824, John Mullett re-surveyed and corrected this line surveying from South to North, calling out old corners and setting new corners at 40 chain intervals and shows the last distance as 90.28 chains for a difference of 5.87 chains. James Blair's 1880± records of each section show the jogs to be to the corrected corners set by John Mullett. The current occupation of roads and the present monumentation of corners and the measurement of the east line

