

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

20 DEC 96 10:56 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Lenawee Located In: Corner Code #
(County)

1. Public Land Survey T - 8-S R - 4-E A-6
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 9 19 96
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*NOTE: SEE COMMENTS & SKETCH ON BACK


G.L.O. This corner was not established by the original government surveyors.
1883, James Blair re-established this corner "Brick, iron & stone" midway between the NW and SW. corners of Section 18.
J.L. Richard record is a copy of J. Blair
July 1973, We dug but didn't find any trace of the corner. Set a 3/4" x 24" iron pipe in line with fence East and on town line and recorded it in L.2, P. 485. (Set corner in line of fence as I believe the fence was built as a result of Blair's survey).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 4, 1996, Found the pavement had been scarified and the iron pipe was gone. I set a 3/4" X 3' gas pipe capped G.E.R. 13040 from the two remaining witnesses from L.2, P. 485 and on line between M-5 & M-7, T8S-R3E.
September 9, 1996, Found the iron pipe under the first course of asphalt and set monument box with top 1 3/4" above the pavement to be level with the top course of asphalt being laid by the Lenawee County Road Commission.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the corner.
Fd. "X" on top of bolt on end of C.M.P. N 5° W 270.47
Fd. "X" on top of bolt on end of C.M.P. N 5° E 289.01
Fd. dbl. hd. nail & disc in Elec. pole S 15° E 90.52
Fd. dbl. hd. nail & disc in Elec. pole S 25° W 53.43
NW. corner Section 18, North 2625.13
SW. corner Section 18, South 2622.42



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-16-1996
Signed by Glenn E. Richard Date 12-19-96
Glenn E. Richard
Surveyor's Michigan License No. 13040

COMMENTS: The G.L.O. Plat maps for T8S-R3E and T8S-R4E are in conflict as to the jogs of the section lines. 1819, Joseph Wampler surveyed the township line from North to South, apparently making an error of approximately 5 chains as he shows the last distance to be 96.15 chains and corrected all temporary corners 16.15 chains South. 1824, John Mullett re-surveyed and corrected this line surveying from South to North, calling out old corners and setting new corners at 40 chain intervals and shows the last distance as 90.28 chains for a difference of 5.87 chains. James Blair's 1880± records of each section show the jogs to be to the corrected corners set by John Mullett. The current occupation of roads and the present monumentation of corners and the measurement of the east line of township fit reasonably well with John Mullett re-survey of the line.

