

# SURVEY & REMONUMENTATION

AUG 10 1998

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 242  
 Filing Requirement of Act 74, Mich. P.A. 1970

## SECTION

For corners in

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T - 8-S R - 4-E	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

1 JUL 98 3:05 P.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on April 7, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Wampler set 1/4 Sec. post R. Oak 6 N 51E 8 Ironwood 7 N 20 W 12  
 1928 The road was surveyed but the notes don't show the corner  
 1969 I set a iron pipe in the pavement for the E 1/4 corner of Section 1 by doubling the distance south from the occupied 1/8 line north to the NE corner of Section 1 on line with found R.R. Spike at the west 1/4 corner of Section 6 T8S R5E  
 1976 Kenneth Suydam found the iron pipe and recorded it in Liber 4 Page 209  
 1980± Lenawee Co. Road Commission rebuilt the road and set a monument box at the iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 7, 1998 I found 1/2" X 38" iron pipe in monument box. Replaced it with a 5/8" X 3' re-bar with Lenawee Co. Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-bar with Len. Co. Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 SW corner of house foundation N 70° W 105.62  
 NE corner of porch foundation N 45° W 81.64  
 "X" cut on CMP S 35° W 36.73  
 Fd dbl hd nail & disc in E.P. S 30° E 54.65  
 A-2 T8S R5E South 44.73

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98  
 Glenn E. Richard

Surveyor's Michigan License No. 13040