

**SURVEY & REMONUMENTATION**

**AUG 10 1998**

Filed under Remonumentation Act 345 of 1990  
**LIBER 1 PAGE 244**

**LAND CORNER RECORDATION CERTIFICATE**

**SECTION**

**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 LENAWEЕ COUNTY  
 FILED

1 JUL 98 3:05 P.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 4-E	M-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on April 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Wampler set 1/4 Sec. post Ash 8 S 43 E 5 Ash 5 N 34 W 17  
 1873 Webb Jipson reestablished the corner "Prorate." Monumentation type not given  
 1889 James Blair set stake in the "found old hole 1.25 1/2 chain north of W 1/4 post Riga"  
 1980 I dug 2' deep and found stone over remains of wood stake. I set iron pipe along east side of stone and recorded it in L 4, P 329  
 1980± Lenawee Co. Road Commission rebuilt the road and set a monument box at the iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 8 I found 1/2" X 3' iron pipe in monument box and replaced it with a 5/8" X 3' re-rod with Lenawee Co. Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee Co. Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 Fd dbl hd nail & disc in E.P. N 20° E 74.38  
 Fd dbl hd nail & disc in E.P. S 5° E 293.19  
 steel fence post S 15° E 92.80  
 Corner of telephone pedestal S 15° E 88.05

A-4 T8S R5E South 82.81



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98  
 Glenn E. Richard

Surveyor's Michigan License No. 13040