

**SURVEY &  
REMONUMENTATION**

**AUG 10 1998**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 1 PAGE 245**

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

1 JUL 98 3:05 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

For corners in SECTION

<u>Lenawee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T - 8-S R - 4- E	M-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on April 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Wampler set post cor. Sec. 12 & 13 Beech 6 S 18 W 22 Hickory 5 N 19 W 11  
1873 Webb Jipson survey Section 12 and called for brick at the corner  
1889 James Blair found stake, stones and bricks at SW corner of Section 7 T8S R5E. Set stake, bricks and glass 2.13 chains (140.58') N 1° 40' W for SE corner Sec. 12 T8S R4E  
1891 James Blair found stake, bricks and glass for survey in Section 13  
1980 I dug and found stone 12" deep. Raised with 1/4" iron bar with top bent so as to be over stone and recorded it in L 4, P 329  
1980± Lenawee Co. Road Commission rebuilt the road and set a monument box at the iron bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 8, 1998 Found 1/4" iron bar in monument box. Removed it and drilled in stone. The drill got hung up so had to split the stone to remove the drill. Set 5/8" X 3' re-rod with Re-mon cap thru stone pieces and bricks under stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee Co. Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
Found dbl hd nail & disc in E.P. N 60° E 31.95  
Center of 5" well casing S 80° E 147.09'  
NE corner of old brick church S 50° E 100.30  
NW corner of new addition on church S 30° E 62.46

A-5 T8S R5E South 140.56



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 9, 1998

Signed by Glenn E. Richard Date 6-26-98  
Glenn E. Richard

Surveyor's Michigan License No. 13040